

June 30, 2020

Vibrating Wire Data Collection Center

1. Delete and replace Paragraph 3.3 of STS M-203-11 – Vibrating Wire Data Collection Center:

3.3 Working Drawing: The Working Drawing shall contain the location of VW-DCC if different from the locations indicated in the plans. Provide written explanation of why the VW-DCC has to be relocated from the locations indicated in the plans with the Working Drawing. Note that a Working Drawing is not required if the VW-DCC is installed at the locations indicated on the plans. Submit Working Drawings for review in accordance with the requirements provided in Section 725 of the Standard Specifications for Highway Construction. Submit the Working Drawings no later than 30 calendar days prior to installation of the VW-DCC(s). Failure to follow the requirements of the Plans, Specifications or this STS may cause delay in processing the submittals. Any subsequent loss of construction time due to failure to follow the requirements as indicated will not be accepted by the Department as a valid reason to change the project's completion date or provide the Contractor with additional time. Do not begin installation of the VW-DCC until the reviewed Working Drawings have been stamped and distributed by the Department for construction. Review and acceptance will be in accordance with Section 725.