



South Carolina
Department of Transportation

DM1202

November 14, 2002

MEMORANDUM TO TEAM LEADERS AND CONSULTANTS

SUBJECT: Concrete Slab Extension

Bridge deck slabs shall be detailed 1 ½ " past the back face of the barrier parapet for slip forming purposes. The transverse reinforcement shall be detailed to maintain 3" clearance from the edge of slab, to allow for construction tolerances. The additional concrete and reinforcing steel shall be included in the quantities shown on the plans.

This change is effective on all future DOT projects. Projects that have been detailed need not be changed.

Randy R. Cannon, P. E.
Bridge Design Engineer

RRC/slb

cc: Assistant Bridge Design Engineers
Bridge Construction Engineer
Gerald Schroeder, FHWA
Director of CRM Operations Walsh
CRM East
CRM West

File: PC/YIA

