



**WORK ZONE TRAFFIC CONTROL
PROCEDURES AND GUIDELINES
FOR
SCDOT
MAINTENANCE ACTIVITIES**

February 1, 2019

WORK ZONE TRAFFIC CONTROL PROCEDURES AND GUIDELINES FOR SCDOT MAINTENANCE ACTIVITIES

Table of Contents

<i>Introduction</i>	1
<i>Roadway Characteristics</i>	2
Roadway Types.....	2
Two-Lane Two-Way.....	2
Multilane.....	2
Interstate.....	2
Roadway Speed Classifications.....	2
Low Speed.....	2
Intermediate Speed.....	2
High Speed.....	2
Traffic Volume Classifications.....	2
Low Volume.....	2
“Rule of Thumb” – Determination of a Low Volume.....	2
Intermediate Volume.....	2
High Volume.....	2
<i>Duration of Work</i>	3
Long-Term Stationary.....	3
Intermediate-Term Stationary.....	3
Short-Term Stationary.....	3
Short Duration.....	3
Mobile.....	3
Intermittent.....	3
Continuous.....	3
<i>Temporary Traffic Control Zone</i>	4
Components.....	4
Advance Warning Area.....	4
Transition Area.....	4
Activity Area.....	4
Termination Area.....	4
Tapers.....	5

Traffic Control Devices.....	7
Signs.....	7
Channelizing Devices.....	9
Standard Traffic Cones.....	9
42" Oversized Traffic Cones.....	9
Portable Plastic Drums.....	9
Barricades.....	9
Warning Lights.....	11
Supplemental Warning Lights for Traffic Control Devices.....	11
Auxiliary Warning Lights for Vehicles and Equipment.....	11
 Trailer Mounted Traffic Control Devices.....	 12
Advance Warning Arrow Panels.....	12
Changeable Message Signs.....	13
 Truck Mounted Traffic Control Devices.....	 14
Advance Warning Arrow Panels.....	14
Changeable Message Signs.....	15
Truck Mounted Attenuators.....	16
 Work Vehicles.....	 17
 Daytime and Nighttime Work.....	 18
 Work Zone Traffic Control Procedures.....	 19
Work Zone Setup / Removal.....	19
Flagging Operations on Two-Lane Two-Way Roadways.....	19
Lane Closures on Multilane Roadways.....	19
Mobile Operations.....	19
Flagging Operations.....	19
Single Flagger Flagging Operations.....	20
Multiple Flaggers Flagging Operations.....	20
Approach Taper.....	20
Downstream Taper.....	20
Flagger Station.....	20
Closed Lane Flagger.....	20
Open Lane Flagger.....	20
Side Road Flagger.....	20
Buffer Space.....	20
Work Activity Area.....	20
Limits of the Work Activity Area.....	20
Approach Lane.....	20
Departure Lane.....	20
Mainline Approach.....	21
Side Road(s).....	21
Limits of the Intersection (Physical Area of an Intersection).....	21
Nighttime Flagging Operations.....	21
Buffer Space.....	22
Signs and Traffic Control Devices.....	22
Advance Warning Arrow Panel.....	23
Truck Mounted Attenuator.....	23
Lane Closures.....	24
Shoulder Closures.....	26

Mobilized Shoulder Operations	27
Primary and Secondary Roadways	27
Pedestrian Workers	27
Equipment / Vehicles	28
Interstate Roadways	28
Mobile Operations	29
Intermittent Mobile Operations	29
Primary and Secondary Routes	29
Interstate Routes	30
Stopping Sight Distance	30
Vehicle Train Requirements	31
Single Work Vehicle	31
Shadow Vehicle	31
Continuous Mobile Operations	32
Detours	33
Pacing Operations	34

Typical Work Zone Traffic Control Standard Drawings for Maintenance Operations

Work Zone Signing

<p>Drawing No. 105-01 Advance Construction Signs Portable Sign Supports Installation.....</p>	<p>WZS-1</p>
<p>Drawing No. 105-10 Work Zone Signing Ground Mounted U-Channel Posts Breakaway System Installation.....</p>	<p>WZS-3</p>
<p>Drawing No. 105-20 Work Zone Signing Ground Mounted U-Channel Posts U-Channel Splice.....</p>	<p>WZS-5</p>
<p>Drawing No. 105-30 Work Zone Signing Square Steel Tube Posts 12 Gauge / 14 Gauge Sign Supports 12 Gauge Ground Support Direct Embedment.....</p>	<p>WZS-7</p>
<p>Drawing No. 105-40 Work Zone Signing Square Steel Tube Posts Typical Single Post Installations Sign Panel Square Footage of 14 Square Feet or Less.....</p>	<p>WZS-9</p>
<p>Drawing No. 105-50 Work Zone Signing Square Steel Tube Posts Single Post Installations 12 Gauge Sign Support 7 Gauge Breakaway Anchors Sign Panels Greater Than 14 Square Feet Up to 20 Square Feet.....</p>	<p>WZS-11</p>
<p>Drawing No. 105-60 Work Zone Signing Square Steel Tube Posts Typical Single Post Installations Sign Panels Greater Than 14 Square Feet Up to 20 Square Feet.....</p>	<p>WZS-13</p>

Lane Closure Installation & Removal

<p>Drawing Nos. 305-01-A 305-01-B 305-02 305-03</p> <p>Lane Closure Installation & Removal Multilane Primary & Secondary Routes Interstate Routes.....</p>	<p>LCIR-1 LCIR-1 LCIR-2</p>
<p> Installation.....</p> <p> Removal.....</p>	<p>LCIR-1 LCIR-2</p>

Flagging Operations

Drawing No. 405-01-A	
Flagging Operations	
Multiple Flaggers	
Two-Lane Two-Way Roadways	
Primary & Secondary Routes.....	FO-1
Scenario – Standard Drawing.....	FO-1
Drawing No. 405-01-B(1)	
Flagging Operations	
Multiple Flaggers	
Two-Lane Two-Way Roadways	
Primary & Secondary Routes	
Stop Sign Controlled Side Roads.....	FO-3
Drawing No. 405-01-B(2)	
Flagging Operations	
Multiple Flaggers	
Two-Lane Two-Way Roadways	
Primary & Secondary Routes	
4-Way Stop Controlled Intersection.....	FO-5
Drawing No. 405-01-C(1)	
Flagging Operations	
Multiple Flaggers	
Two-Lane Two-Way Roadways	
Primary & Secondary Routes	
Traffic Signal Controlled Intersection	
Law Enforcement Officer(s).....	FO-7
Drawing No. 405-01-C(2)	
Flagging Operations	
Multiple Flaggers	
Two-Lane Two-Way Roadways	
Primary & Secondary Routes	
Traffic Signal Controlled Intersection	
Flaggers.....	FO-9
Drawing No. 405-01-D(1)	
Flagging Operations	
Multiple Flaggers	
Two-Lane Two-Way Roadways	
Primary & Secondary Routes	
Work Activity Area	
Beginning at an	
Intersection with a	
Two-Lane Two-Way Roadway	
Departure Lane.....	FO-11
Drawing No. 405-01-D(2)	
Flagging Operations	
Multiple Flaggers	
Two-Lane Two-Way Roadways	
Primary & Secondary Routes	
Work Activity Area	
Terminating at an	
Intersection with a	
Two-Lane Two-Way Roadway	
Approach Lane.....	FO-15

Drawing Nos. 405-01-E(1)
Flagging Operations
Multiple Flaggers
Two-Lane Two-Way Roadways
Primary & Secondary Routes
Work Activity Area
Intersections with
Low Speed
< / = 35 MPH
Multilane Roadways..... **FO-18**

Drawing Nos. 405-01-E(2)
Flagging Operations
Multiple Flaggers
Two-Lane Two-Way Roadways
Primary & Secondary Routes
Work Activity Area
Intersections with
Low Speed
< / = 35 MPH
Multilane Roadways..... **FO-20**

Drawing Nos. 405-01-F(1)
Flagging Operations
Multiple Flaggers
Two-Lane Two-Way Roadways
Primary & Secondary Routes
Work Activity Area
Intersections with
Intermediate Speed to High Speed
40 MPH – 60 MPH
Multilane Roadways..... **FO-22**

Drawing Nos. 405-01-F(2)
Flagging Operations
Multiple Flaggers
Two-Lane Two-Way Roadways
Primary & Secondary Routes
Work Activity Area
Intersections with
Intermediate Speed to High Speed
40 MPH – 60 MPH
Multilane Roadways..... **FO-25**

Drawing No. 405-02
Flagging Operations
Single Flagger Operation
Low Volume
Low Speed to Intermediate Speed
Two-Lane Two-Way Roadways
Primary & Secondary Routes..... **FO-27**

Lane Closures
Primary & Secondary Routes

Drawing No. 505-01
Lane Closure
Low Speed Multilane
< / = 35 MPH
Primary & Secondary Routes..... **LCPS-1**

Drawing No. 505-02 Dual Lane Closure Low Speed Multilane < / = 35 MPH Primary & Secondary Routes.....	LCPS-4
Drawing No. 505-03-A Lane Closure Intermediate Speed to High Speed 40 MPH – 60 MPH Multilane Primary & Secondary Routes.....	LCPS-7
Drawing No. 505-03-B Lane Closure Intermediate Speed to High Speed 40 MPH – 60 MPH Exit / Entrance Ramps Multilane Primary & Secondary Routes.....	LCPS-10
Drawing Nos. 505-04-A 505-04-B Dual Lane Closure Intermediate Speed to High Speed 40 MPH – 60 MPH Transition / Activity Areas / Advance Warning Area Multilane Primary & Secondary Routes.....	LCPS-12
Drawing No. 505-04-C Dual Lane Closure Intermediate Speed to High Speed 40 MPH – 60 MPH Exit / Entrance Ramps Multilane Primary & Secondary Routes.....	LCPS-16

**Lane Closures
Interstate Routes**

Drawing No. 510-01-A Lane Closure Interstate Routes.....	LCI-1
Drawing No. 510-01-B Lane Closure Exit / Entrance Ramps Interstate Routes.....	LCI-4
Drawing Nos. 510-02-A 510-02-B Dual Lane Closure Transition / Activity Areas / Advance Warning Area Interstate Routes.....	LCI-6
Drawing No. 510-02-C Dual Lane Closure Exit / Entrance Ramps Interstate Routes.....	LCI-10

Shoulder Closures Primary & Secondary Routes

Drawing No. 515-01-A Right Shoulder Closure (Case I / Case II) Two-Lane Two-Way Roadway Primary & Secondary Routes.....	SCPS-1
Drawing No. 515-01-B Right Shoulder Closure (Case I / Case II) Multilane Primary & Secondary Routes.....	SCPS-3
Drawing No. 515-01-C Right Shoulder Closure Low Speed < / = 35 MPH Primary & Secondary Routes (Minor Encroachment).....	SCPS-5
Drawing No. 515-01-D Left Shoulder Closure Low Speed < / = 35 MPH Multilane Divided Highway with Grassed Earth Median Primary & Secondary Routes (Minor Encroachment).....	SCPS-7
Drawing No. 515-02 Left Shoulder Closure (Case I / Case I) Multilane Primary & Secondary Routes.....	SCPS-9
Drawing No. 515-03 Left Shoulder Closure (Case I / Case II) Multilane Primary & Secondary Routes.....	SCPS-11

Shoulder Closures Interstate Routes

Drawing No. 520-01 Right Shoulder Closure (Case I / Case II) Interstate Routes.....	SCI-1
Drawing No. 520-02 Left Shoulder Closure (Case I / Case I) Narrow Median Interstate Routes.....	SCI-3
Drawing No. 520-03 Left Shoulder Closure (Case I / Case I) Wide Median Interstate Routes.....	SCI-5

Drawing No. 520-04 Left Shoulder Closure (Case I / Case II) Wide Median Interstate Routes.....	SCI-7
Drawing No. 520-05 Left Shoulder Closure (Case II / Case II) Wide Median Interstate Routes.....	SCI-9
Drawing No. 520-06 Gore Area Interstate Routes.....	SCI-11

**Mobilized Shoulder Operations
Primary & Secondary Routes**

Drawing No. 525-01 Mobilized Shoulder Operations Road Machinery – Minor Encroachment Primary & Secondary Routes.....	MSOPS-1
Drawing No. 525-02 Mobilized Shoulder Operations Pedestrian Workers – No Encroachment Road Machinery – Minor Encroachment Primary & Secondary Routes.....	MSOPS-3
Drawing No. 525-03 Mobilized Shoulder Operations Road Machinery – Major Encroachment Primary & Secondary Routes.....	MSOPS-5
Drawing No. 525-04 Mobilized Shoulder Operations Intermediate Speed to High Speed 40 MPH – 60 MPH Pedestrian Workers - Major Encroachment Road Machinery - Major Encroachment Multilane Primary & Secondary Routes.....	MSOP-7

**Mobilized Shoulder Operations
Interstate Routes**

Drawing No. 530-01 Mobilized Shoulder Operations Road Machinery – Major Encroachment Interstate Routes.....	MSOI-1
Drawing No. 530-02 Mobilized Shoulder Operations Pedestrian Workers – Minor Encroachment Upon Paved Shoulder Interstate Routes.....	MSOI-3
Drawing No. 530-03 Mobilized Shoulder Operations Pedestrian Workers – Major Encroachment Upon Paved Shoulder Road Machinery – Major Encroachment Upon Travel Lane Interstate Routes.....	MSOI-5

**Mobile Operations
Intermittent**

Drawing Nos. 535-01-A 535-01-B	
Mobile Operations Intermittent Stopping Sight Distance Vehicle Train Requirements	
Vertical Curve (Hill) / Horizontal Curve (Curve).....	MOI-1
Vehicle Train Requirements.....	MOI-2
Single Work Vehicle.....	MOI-2
Shadow Vehicle.....	MOI-2
 Drawing Nos. 535-02-A 535-02-B	
Mobile Operations Intermittent Low Volume Low Speed / Intermediate Speed to High Speed	
Primary & Secondary Routes.....	MOI-5
 Drawing Nos. 535-03-A 535-03-B	
Mobile Operations Intermittent Intermediate Volume Low Speed / Intermediate Speed to High Speed	
Primary & Secondary Routes.....	MOI-8
 Drawing No. 535-04-A	
Mobile Operations Intermittent High Volume Low Speed	
Primary & Secondary Routes.....	MOI-11
 Drawing No. 535-04-B	
Mobile Operations Intermittent High Volume Low Speed Interior Travel Lane Operations	
Primary & Secondary Routes.....	MOI-13
 Drawing No. 535-04-C	
Mobile Operations Intermittent High Volume Intermediate Speed to High Speed	
Primary & Secondary Routes.....	MOI-15
 Drawing No. 535-04-D(1)	
Mobile Operations Intermittent High Volume High Speed	
Interstate Routes.....	MOI-17
 Drawing No. 535-04-D(2)	
Mobile Operations Intermittent Pedestrian Workers Interstate Routes (Major Encroachment).....	
	MOI-19

Drawing No. 535-04-E Mobile Operations Intermittent High Volume High Speed Interior Travel Lane Operations Interstate Routes.....	MOI-22
---	--------

**Mobile Operations
Continuous**

Drawing No. 540-01 Mobile Operations Continuous Two-Lane Two-Way Roadways Primary & Secondary Routes.....	MOC-1
---	-------

Drawing Nos. 540-02-A 540-02-B Mobile Operations Continuous Multilane Primary & Secondary Routes Earth Median with Grassed or Paved Shoulders / Paved Median with Curb & Gutter.....	MOC-3
--	-------

Drawing Nos. 540-03-A 540-03-B Mobile Operations Continuous Interstate Routes Right Travel Lane / Left Travel Lane.....	MOC-6
--	-------

Drawing Nos. 540-04-A 540-04-B Mobile Operations Continuous Dual Lane Closures Interior Travel Lane Operations Interstate Routes Right Travel Lanes / Left Travel Lanes.....	MOC-9
---	-------

**Traffic Signal Work Operations
Signal Heads**

Drawing No. 605-01-A Traffic Signal Work Operations Vehicle Train Two-Lane Two-Way Roadway Primary & Secondary Routes Traffic Signal Work Activities Completed in 15 Minutes or Less.....	TSSH-1
--	--------

Drawing No. 605-01-B Traffic Signal Work Operations Vehicle Train Two-Lane Two-Way Roadway Primary & Secondary Routes Traffic Signal Work Activities That Exceed a Time Duration of 15 Minutes.....	TSSH-3
--	--------

Drawing No. 605-02-A Traffic Signal Work Operations Vehicle Train Right Lane Closure Multilane Primary & Secondary Routes Traffic Signal Work Activities Completed in 15 Minutes or Less.....	TSSH-5
Drawing No. 605-02-B Traffic Signal Work Operations Vehicle Train Right Lane Closure Multilane Primary & Secondary Routes Traffic Signal Work Activities That Exceed a Time Duration of 15 Minutes But Not More Than 60 Minutes.....	TSSH-7
Drawing No. 605-03-A Traffic Signal Work Operations Vehicle Train Interior Lane Closure Multilane Primary & Secondary Routes with 2 Through Lanes Traffic Signal Work Activities Completed in 15 Minutes or Less.....	TSSH-9
Drawing No. 605-03-B Traffic Signal Work Operations Vehicle Train Interior Lane Closure Multilane Primary & Secondary Routes with 2 Through Lanes Traffic Signal Work Activities That Exceed a Time Duration of 15 Minutes But Not More Than 60 Minutes.....	TSSH-11
Drawing No. 605-04-A Traffic Signal Work Operations Vehicle Train Interior Lane Closure Multilane Primary & Secondary Routes with 3 or More Through Lanes Traffic Signal Work Activities Completed in 15 Minutes or Less.....	TSSH-13
Drawing No. 605-04-B Traffic Signal Work Operations Vehicle Train Interior Lane Closure Multilane Primary & Secondary Routes with 3 or More Through Lanes Traffic Signal Work Activities That Exceed a Time Duration of 15 Minutes But Not More Than 60 Minutes.....	TSSH-15
Drawing No. 605-05-A(1) Traffic Signal Work Operations Side Street Treatment Dual Left Turn Lanes Work Vehicle – Right Lane Multilane Primary & Secondary Routes Traffic Signal Work Activities Completed in 15 Minutes or Less.....	TSSH-17

Drawing No. 605-05-A(2)
 Traffic Signal Work Operations
 Side Street Treatment
 Dual Left Turn Lanes
 Work Vehicle – Left Lane
 Multilane
 Primary & Secondary Routes
 Traffic Signal Work Activities Completed in 15 Minutes or Less..... TSSH-19

Drawing No. 605-05-B(1)
 Traffic Signal Work Operations
 Side Street Treatment
 Dual Left Turn Lanes
 Work Vehicle – Right Lane
 Multilane
 Primary & Secondary Routes
 Traffic Signal Work Activities That Exceed a Time Duration of 15 Minutes
 But Not More Than 60 Minutes..... TSSH-21

Drawing No. 605-05-B(2)
 Traffic Signal Work Operations
 Side Street Treatment
 Dual Left Turn Lanes
 Work Vehicle – Left Lane
 Multilane
 Primary & Secondary Routes
 Traffic Signal Work Activities That Exceed a Time Duration of 15 Minutes
 But Not More Than 60 Minutes..... TSSH-23

**Traffic Signal Work Operations
 Loops**

Drawing No. 606-01
 Traffic Signal Work Operations
 Vehicle Train
 Two-Lane Two-Way Roadway
 Primary & Secondary Routes
 Traffic Signal Detection Loop Installation
 Stop Bar Loops..... TSL-1

Drawing No. 606-02
 Traffic Signal Work Operations
 Vehicle Train
 Two-Lane Two-Way Roadway
 Primary & Secondary Routes
 Traffic Signal Detection Loop Installation
 Set Back Loops..... TSL-3

Drawing No. 606-03
 Traffic Signal Work Operations
 Vehicle Train
 Right Lane Closure
 Multilane
 Primary & Secondary Routes
 Traffic Signal Detection Loop Installation
 Stop Bar Loops..... TSL-5

Drawing No. 606-04-A
Traffic Signal Work Operations
Vehicle Train
Interior Lane Closure
Multilane
Primary & Secondary Routes with 2 Through Lanes
Traffic Signal Detection Loop Installation
Stop Bar Loops..... **TSL-7**

Drawing No. 606-04-B
Traffic Signal Work Operations
Vehicle Train
Interior Lane Closure
Multilane
Primary & Secondary Routes with 2 Through Lanes
Connecting The Stop Bar Loop to The Pull Box..... **TSL-9**

Drawing No. 606-05-A
Traffic Signal Work Operations
Vehicle Train
Interior Lane Closure
Multilane
Primary & Secondary Routes with 3 or More Through Lanes
Traffic Signal Detection Loop Installation
Stop Bar Loops..... **TSL-11**

Drawing No. 606-05-B
Traffic Signal Work Operations
Vehicle Train
Interior Lane Closure
Multilane
Primary & Secondary Routes with 3 or More Through Lanes
Connecting The Stop Bar Loop to The Pull Box..... **TSL-13**

Drawing No. 606-06
Traffic Signal Work Operations
Vehicle Train
Right Lane Closure
Multilane
Primary & Secondary Routes with 2 Through Lanes
Traffic Signal Detection Loop Installation
Set Back Loops..... **TSL-15**

Drawing No. 606-07
Traffic Signal Work Operations
Vehicle Train
Right Lane Closure
Multilane
Primary & Secondary Routes with 3 or More Through Lanes
Traffic Signal Detection Loop Installation
Set Back Loops..... **TSL-17**

**Pavement Marking Application
Operations**

Drawing No. 610-01
Pavement Marking Application
Intersections
Vehicle Train
Two-Lane Two-Way Roadway
Primary & Secondary Routes..... **PMO-1**

Drawing No. 610-02
Pavement Marking Application
Intersections
Vehicle Train
Right Lane Closure
Multilane..... **PMO-3**

Drawing No. 610-03
Pavement Marking Application
Intersections
Vehicle Train
Interior Lane Closure
Multilane
2 Through Lanes..... **PMO-5**

Drawing No. 610-04
Pavement Marking Application
Intersections
Vehicle Train
Interior Lane Closure
Multilane
2 or More Through Lanes..... **PMO-7**

**Extended
Road Closures**

Drawing No. 705-01
Extended Road Closure of Roadway..... **ERC-1**

Drawing No. 705-02
Extended Road Closure for Bridge Work..... **ERC-3**

Detour Signing

Drawing No. 805-01
Detour Signing for Primary and Interstate Routes..... **DS-1**

Drawing No. 805-02
Detour Signing for Secondary Routes..... **DS-3**

Traffic Control Requirements for Specific Maintenance Performance Activities

Performance Activity 102 Surface Repairs

102	Surface Repairs		102-1
	Work Description 1	Patching / Minor Leveling.....	102-1
	Work Description 2	Major Leveling / Strengthening.....	102-6
	Work Description 3	Resurface.....	102-8

Performance Activity 107 Chip Seal

107	Chip Seal		107-1
	Work Description 1	Single.....	107-1
	Work Description 2	Double.....	107-1
	Work Description 3	Triple.....	107-1

Performance Activity 108 Milling

108	Milling		108-1
-----	----------------------	--	-------

Performance Activity 110 Base Repair

110	Base Repair		110-1
	Work Description 1	Full Depth Asphalt.....	110-1
	Work Description 2	Full Depth Concrete.....	110-1
	Work Description 3	Reclamation.....	110-4

Performance Activity 120 Crack Seal Pavement

120	Crack Seal Pavement		120-1
	Work Description 1	Asphalt.....	120-1
	Work Description 2	Concrete.....	120-1

Performance Activity 130 Earth Roads

130	Earth Roads		130-1
	Work Description 1	Machining Earth Roads.....	130-1
	Work Description 2	Dust Control.....	130-1

Performance Activity 202 Slopes

202	Slopes		202-1
	Work Description 1	Repair.....	202-1
	Work Description 2	Install / Maintain.....	202-1

**Performance Activity 203
Shoulders / Ditches**

203	Shoulders / Ditches.....		203-1
	Work Description 1	Clean Outfall.....	203-1
	Work Description 2	Construct Outfall.....	203-1
	Work Description 3	Regrade Roadside Ditch.....	203-5
	Work Description 4	Regrade / Repair Shoulder.....	203-5
	Work Description 5	Regrade Shoulder and Ditch.....	203-5
	Work Description 6	Widen Shoulder.....	203-5

**Performance Activity 204
Construction / Paving**

204	Construction / Paving.....		204-1
	Work Description 1	Pavement Widening / Turn Lanes.....	204-1
	Work Description 2	Shoulder Paving.....	204-1
	Work Description 3	Median Paving (Crossover).....	204-1

**Performance Activity 305
Drainage Structures**

305	Drainage Structures.....		305-1
	Work Description 1	Repair.....	305-1
	Work Description 2	Install.....	305-1
	Work Description 3	Upgrade.....	305-1
	Work Description 4	Clean.....	305-1

**Performance Activity 306
Drainage Pipe**

306	Drainage Pipe.....		306-1
	Work Description 1	Repair.....	306-1
	Work Description 2	Install.....	306-1
	Work Description 3	Remove.....	306-1
	Work Description 4	Clean.....	306-1

**Performance Activity 401
Mowing**

401	Mowing.....		401-1
	Work Description 1	Brush Management.....	401-1
	Work Description 2	Hand Trimming.....	401-1
	Work Description 3	Outdoor Advertising Window.....	401-1
	Work Description 5	Safety.....	401-1
	Work Description 4	Routine.....	401-6

**Performance Activity 402
Herbicide Application**

402	Herbicide.....		402-1
	Work Description 1	Total Vegetation Control.....	402-1
	Work Description 2	Brush.....	402-1
	Work Description 3	Trees.....	402-1
	Work Description 4	Broadleaf Weeds.....	402-1
	Work Description 5	Grassy Weeds.....	402-1
	Work Description 6	Turf.....	402-1

**Performance Activity 403
Grassing**

403	Grassing.....	403-1
-----	---------------	-------

**Performance Activity 405
Limb Management**

405	Limb Management.....	405-1
-----	----------------------	-------

**Performance Activity 406
Beautification**

406	Beautification.....	406-1
-----	---------------------	-------

**Performance Activity 407
Litter Control**

407	Litter Control.....	407-1
	Work Description 1 Litter.....	407-1
	Work Description 2 Dead Animals.....	407-4
	Work Description 3 Litter Bag Pickup.....	407-7

**Performance Activity 408
Tree Removal**

408	Tree Removal.....	408-1
	Work Description 1 Fallen Tree.....	408-1
	Work Description 2 Standing Tree.....	408-1

**Performance Activity 409
Debris Removal**

409	Debris Removal.....	409-1
	Work Description 1 Vegetation.....	409-1
	Work Description 2 Construction / Demolition.....	409-1
	Work Description 3 Personal Property / Household Items.....	409-1
	Work Description 4 White Goods.....	409-1
	Work Description 5 Soil, Mud, Sand.....	409-1
	Work Description 6 Vehicles / Vessels.....	409-1
	Work Description 7 Hazardous Waste.....	409-5

**Performance Activity 410
Roadway Cleaning**

410	Roadway Cleaning.....	410-1
	Work Description 1 Clean by Hand.....	410-1
	Work Description 2 Clean by Machine.....	410-5

**Performance Activity 501
Driveways**

501	Driveways.....	501-1
	Work Description 1 Install.....	501-1
	Work Description 2 Remove.....	501-1
	Work Description 3 Maintenance.....	501-1

**Performance Activity 504
Concrete Structures**

504	Concrete Structures.....		504-1
	Work Description 1	Curb Ramp - Install.....	504-1
	Work Description 2	Sidewalk – Repair.....	504-1
	Work Description 3	Install.....	504-1
	Work Description 4	Repair.....	504-1
	Work Description 5	Remove.....	504-1

**Performance Activity 603
Signs**

603	Signs.....		603-1
	Work Description 3	New Install.....	603-1
	Work Description 4	Maintenance / Replace.....	603-1
	Work Description 6	Temporary.....	603-1

**Performance Activity 604
Traffic Signal**

604	Traffic Signal.....		604-1
	Work Description 1	Trouble Call.....	604-1
	Work Description 2	Rebuild.....	604-1
	Work Description 3	Install.....	604-1
	Work Description 4	Revise.....	604-1
	Work Description 5	Repair.....	604-1
	Work Description 6	Preventative Maintenance Inspection.....	604-1
	Work Description 7	Contract Inspection.....	604-1

**Performance Activity 605
Flashers**

605	Flashers.....		605-1
	Work Description 1	Trouble Call.....	605-1
	Work Description 2	Rebuild.....	605-1
	Work Description 3	Install.....	605-1
	Work Description 4	Revise.....	605-1
	Work Description 5	Repair.....	605-1
	Work Description 6	Preventative Maintenance Inspection.....	605-1
	Work Description 7	Contract Inspection.....	605-1
	Shoulder - Structure Mounted		605-1
	Overhead - Span Wire Mounted		605-6

**Performance Activity 606
Pavement Striping**

606	Pavement Striping.....		606-1
	Work Description 1	New Install / Revise.....	606-1
	Work Description 2	Remove.....	606-1
	Work Description 3	Replace.....	606-1

**Performance Activity 607
Hand Placed Markings**

607	Hand Placed Markings.....		607-1
	Work Description 1	New Install / Revise.....	607-1
	Work Description 2	Remove.....	607-1
	Work Description 3	Replace.....	607-1

**Performance Activity 610
Guardrail**

610	Guardrail.....		610-1
	Work Description 1	Repair.....	610-1
	Work Description 2	Install.....	610-1
	Work Description 3	Remove.....	610-1

**Performance Activity 611
Walls / Fences**

611	Walls / Fences.....		611-1
	Work Description 1	Repair.....	611-1
	Work Description 2	Install.....	611-1
	Work Description 3	Remove.....	611-1

**Performance Activity 613
Impact Attenuator**

613	Impact Attenuator.....		613-1
	Work Description 1	Install.....	613-1
	Work Description 2	Remove.....	613-1
	Work Description 3	Repair.....	613-1

**Performance Activity 614
Highway Lighting**

614	Highway Lighting.....		614-1
	Work Description 1	Install.....	614-1
	Work Description 2	Repair.....	614-1
	Work Description 3	Inspection.....	614-1

**Performance Activity 701
Hazardous Conditions**

701	Hazardous Conditions.....		701-1
	Work Description 1	Winter Weather Operations.....	701-1
	Work Description 3	Preparation.....	701-1
	Work Description 4	Roadway Clearing.....	701-2
	Work Description 2	Spill Response.....	701-5

**Performance Activity 800
Bridge Construction**

800	Bridge Construction.....		800-1
	Work Description 1	Rebuild Existing.....	800-1
	Work Description 2	Replace.....	800-1

**Performance Activity 801
Deck Repair**

801	Deck Repair.....		801-1
	Work Description 1	Concrete Deck Repair.....	801-1
	Work Description 2	Non-Concrete Repair.....	801-1

**Performance Activity 802
Bridge Rail Repair**

802	Bridge Rail Repair.....	801-1
-----	-------------------------	-------

**Performance Activity 803
Superstructure Element**

803	Superstructure Element.....	803-1
	Work Description 1 Beams.....	803-1
	Work Description 2 Floor Beams.....	803-1
	Work Description 3 Stringers.....	803-1
	Work Description 4 Truss Chords.....	803-1

**Performance Activity 805
Bridge Expansion Joints**

805	Bridge Expansion Joints.....	805-1
	Work Description 1 Compression Seal.....	805-1
	Work Description 2 Cold Poured Seal.....	805-1

**Performance Activity 806
Bearing and Saddles**

806	Bearing and Saddles.....	806-1
	Work Description 1 Repair Elastomeric Bearing.....	806-1
	Work Description 2 Replace Elastomeric Bearing.....	806-1
	Work Description 3 Repair Steel Bearing Assembly.....	806-1
	Work Description 4 Replace Steel Bearing Assembly.....	806-1
	Work Description 5 Steel Saddle – Individual.....	806-1
	Work Description 6 Steel Saddle – Continuous.....	806-1

**Performance Activity 807
Bridge Maintenance**

807	Bridge Maintenance.....	807-1
	Work Description 1 Debris Removal.....	807-1
	Work Description 2 Electrical Repair / Inspection.....	807-1
	Work Description 3 Mechanical Repair.....	807-1
	Work Description 4 Scour Remediation.....	807-1
	Work Description 5 Clean Weep Holes.....	807-1
	Work Description 6 Clean Bearing Assemblies / Caps.....	807-1
	Work Description 7 Fender Repair.....	807-1

**Performance Activity 809
Bridge Piles and Caps**

809	Bridge Piles and Caps.....	809-1
	Work Description 1 Cap Repair.....	809-1
	Work Description 2 Cap Replacement.....	809-1
	Work Description 3 Pile Repair.....	809-1
	Work Description 4 Pile Replacement.....	809-1

**Performance Activity 815
Bridge Inspection**

815	Bridge Inspection.....	815-1
	Work Description 1 Bridge Inspection.....	815-1
	Work Description 2 Overhead Sign Inspection.....	815-1

Tables

Table 1. Formulas for Determining Taper Lengths..... 5

Table 2. Taper Types and Taper Length Criteria..... 6

Table 3. Advance Warning Sign Placement Intervals for a Typical 3 Advance Warning Sign Array..... 8

Table 4. Traffic Control Channelizing Device Applications..... 10

Table 5. Advance Warning Arrow Panels (Trailer Mounted)..... 12

Table 6. Advance Warning Arrow Panels (Truck Mounted)..... 14

Table 7. Work Area Illumination Requirements..... 18

Table 8. Traffic Stopped Time Durations for Flagging Operations..... 19

Table 9. Minimum Distance Requirements for a Buffer Space in a Flagging Operation 22

Table 10. Traffic Control Device Spacing Intervals for Flagging Operations..... 23

Table 11. Stopping Sight Distance..... 30

Table 12. Departure Lane from the Intersection
Minimum Distance Intervals from Intersection Required for Conversion to Standard Multiple Flagger Flagging Operation Installation per Drawing No. 405-01-D(1)..... FO-12

Table 13. Approach Lane to the Intersection
Minimum Distance Intervals from Intersection Required for Conversion from a Standard Multiple Flagger Flagging Operation Installation per Drawing No. 405-01-D(2)..... FO-16

Table 14. Advance Warning Sign Placement Intervals for Single Flagger Operations (Drawing No. 405-02)..... FO-27

Table 15. Shadow Vehicle / Work Vehicle Distance Intervals..... MOI-1

Table 16. Traffic Control Devices Quantities for Extended Road Closure of Roadway (Single Approach) (Drawing No. 705-01)..... ERC-1

Table 17. Traffic Control Devices Quantities for Extended Road Closure - Bridge Work (Single Approach) (Drawing No. 705-02)..... ERC-3

Table 18. Detour Sign Assembly Guidelines for Lateral Location (Primary and Interstate Routes) (Drawing No. 805-01)..... DS-1

Table 19. Detour Sign Assembly Guidelines for Lateral Location (Secondary Routes) (Drawing No. 805-02)..... DS-3